BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/16/2019-20 Dated:31-01-2020

APPROVED TENDER SCHEDULE –'B'

Item-05

Name of Work:-Construction and Developments of roads in kempegowda ward no -01 of yelahanka Sub division

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri Sri R LOKESH (RAMAIAH LOKESH)	
				Rate	Rate in Words
1	KSRRB 300-1. excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatl dressed the disposed earth to be levelled neatly after breaking of colds complee as per specifications MORTH/ Chapter 3 (KPWD SR 2018-19	Cum	483.12	215.00	Rupees Two Hundred Fifteen Only
2	KSRB 4-1.2 : Providing and laying in position plain cement concrete of Mix 1:3:6 with OPC @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM curing complete as per specifications. (P.No-13,I No-4.2,KPWD SR 2018-19)	Cum	73.20	5725.00	Rupees Five Thousand Seven Hundred Twenty Five Only
3	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. With 20mm and sown size granite metal course aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compcted for walls and bottom including centring shuttering cost of material HOM of machinary curing etc., complete execluding cost of steel as per MORTH specification no. 1500, 1700, 2200 including cost of material labour HOM complete as per specification..and site engineer in incharge	Cum	175.68	7350.00	Rupees Seven Thousand Three Hundred Fifty Only
4	Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, palcing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining memebrs wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications .and site engineer in incharge	Tonne	10.54	77000.00	Rupees Seventy Seven Thousand Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri Sri R LOKESH (RAMAIAH LOKESH)	
				Rate	Rate in Words
5	Providing and fixing RCC precast cover slab of 100mm thick for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate)	Sqm	439.20	2430.00	Rupees Two Thousand Four Hundred Thirty Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.